

INSTALLATION AND MAINTENANCE INSTRUCTIONS

403-0006 SITA MANUAL CALL POINT



http://www.fike.co.uk/ resource-downloads/addressable/

General Description

The Sita Manual Call Point allows for user activation of the fire alarm system. Once operated the device latches into the alarm position and requires manually resetting via a special key. The MCP is an addressable unit that attaches to the loop. Digital communication technology to the control panel is implemented allowing for accurate data transfer at high transmission speeds.

Before Installation

The MCP must be installed in compliance with the control panel installation manual. The installation must also meet the requirements of any local authority.

Spacing

Fike recommends spacing of call points in accordance with any local authority.

Device Installation

All wiring must be installed in compliance with the recommendations laid out by any local authority as well as any special recommendations documented in the control panel installation manual. All wiring must be installed in compliance with the recommendations laid out by any local authority as well as any special recommendations documented in the control panel installation manual. The cabling used should be of a 2-core 1.5mm² screened, fire resistant type, with the following characteristics:

Max Capacitance Core to Screen	. 180pF / m
Max Capacitance Core to Core	.100pF / m
Max Inductance	
Max Resistance Two Core Screened 1.5mm ²	.12.1Ω / km

It is to be wired in the form of a screened 2-core loop returning to the control panel. The use of spurs on this system is not permitted. Cables may be terminated into the connectors, as shown overleaf. If the device is flush mounted then the loop cabling must be attached to the device via a suitable connection block (not supplied). Cut off crimp fork terminals, strip ends for desired length and twist conductor strands together neatly as shown below. Terminate your cables directly into a flying terminal block. If using a metal back box, do not connect the screen to the back box earth terminal or allow it to come into contact with the metal box



Document No. 26-1075 Issue 6 Subject to change





Care should be taken when terminating devices to ensure all cables are correctly sleeved and connections are secure. Improper connections will prevent a system from responding properly in the event of a fire.



Terminal	Description
R (RED)	Loop +ve IN
Y (YELLOW)	Loop +ve OUT
B (BLUE)	Loop -ve IN & OUT
E	Loop SCREEN IN & OUT

The Loop +ve (positive) IN and the Loop +ve (positive) OUT connections are split within the module. For cable continuity readings at the commissioning stage they must be temporarily removed and connected through. Please remember that all high voltage testing must be carried out before the installation of the electronics, otherwise the electronics will be damaged. Please also note that the E terminal should only be connected to the loop screen and NOT to the building earth.

Once all testing has been carried out on the cabling and **continuity & insulation** has been proven, the MCP can be connected, with each of the three wires from the MCP front being connected to the corresponding terminal in the backbox according to the wire colour. The MCP front may then be installed by locating the upper mounting hook into the receiver in the back box and then pushing the unit gently home. The single fixing screw may then be tightened as required.

NOTE: Before installing the MCP remember to note the serial number of the device (located on the rear of the unit) on to your drawings or configuration sheets to enable you to prove its location later. The address allocation for the device is carried out automatically by the control panel whilst in initialisation mode, so addresses do not need to be set manually. See the system Installation and Operating Instructions for further details.

Reset and Test

The Manual Call Point contains a re-settable element, which latches in position when operated and does not need to be replaced. Inserting the key as shown and turning it clockwise until the element clicks back into place will reset the unit. Testing the Call Point may be carried out either by pressing the element or by using the key in the same manner as for resetting but without having pressed the element

Technical Data

Dimensions:	Width x Height Depth: Standard inc base Depth: Flush mounted	87mm x 87mm 53mm 25mm		
Flush Back Box Dimensions:	Required Minimum Depth	47mm		
Operating Temperature:		-10°C to +50°C.		
Voltage Range (Loop):		24 to 42V DC		
LED Indication:	Activated	0.3s interval		
Flammability		UL94-V2		
IP Rating		IP 21C		
System Compatibility:	Sita200plus V2.00 onwards.			
	Duonet and Quadnet V1 onwards.			
	CIE-A-200 V1 onwards			







Technical Data

PRODUCT DESCRIPTION		LOOP CURRENT (mA)					
Туре	Product Code	Name	Quiescent	Alarm	Low	Medium	High
MCP	403 0006	Sita Manual Call Point Mk3	0.18	2.89	-	-	-

			BATTERY CURRENT (mA)				
Туре	Product Code	Name	Quiescent	Alarm	Low	Medium	High
MCP	403 0006	Sita Manual Call Point Mk3	0.18	6.00	-	-	-

			DLU RATING			
Туре	Product Code	Name	Alarm	Low	Medium	High
MCP	403 0006	Sita Manual Call Point Mk3	3	-	-	-

Technical Support

Contact your supplier for technical support on this product.

Due to the complexity and inherent importance of a life risk type system training on this equipment is essential, and commissioning should only be carried out by competent persons. Fike cannot guarantee the operation of any equipment unless all documented instructions are complied with, without variation.

Fike's policy is one of continual improvement and the right to change a specification at any time without notice is reserved. Whilst every care has been taken to ensure that the contents of this document are correct at time of publication, Fike shall be under no liability whatsoever in respect of such contents. E&OE





Fike Safety Technology Ltd Unit 31, Springvale Industrial Estate Cwmbran NP44 5BD Tel: 01633 865 558 | Email: fstinfo@fike.com

Document No. 26-1075 Issue 6 Subject to change